

EXECUTANT:

BENEFICIAR:
PRIMARIA VETIS

LISTA CANTITATI / LUCRARI

EXTINDERE (PROIECTARE+EXECUTIE)			TOTAL
1	BUC	1	1.00
<i>PROIECT TEHNIC EXTINDERE RETEA LOC. DECEBAL, VETIS, OAR (VA INCLUDE DTAC, PT SI DE)</i>			
2	ML	6479	6479.00
<i>TEAVA GAZ PE 100 DN 63 (MATERIAL+MANOPERA)</i>			
3	ML	6479	6479.00
<i>ACCESORII (FIR TRASOR, BANDA GAZ, PLACUTE SEMNALIZARE, MANOPERA MONTAJ)</i>			
4	BUC	145	145.00
<i>MUFA /DOP /COT /TEU ELECTROFUZIUNE PE100 DN 63-90-110 (MATERIAL+MANOPERA MONTAJ/SUDURA)</i>			
5	BUC	1	1.00
<i>PROBE DE PRESIUNE DE CASA</i>			
6	BUC	1	1.00
<i>PROBE DE PRESIUNE CU DIAGRAMA SI ASISTENTA GAZ VEST (SE VA EFECTUA CONFORM CERINTE DISTRIBUTOR GAZ VEST)</i>			
7	BUC	1	1.00
<i>INTOCMIT CARTEA CONSTRUCTIEI SI DOSAR PTR.PREDARE GAZ VEST</i>			
8	ML	6479	6479.00
<i>SAPATURA MECANIZATA+ASTUPAT (VA INCLUDE SAPATURA, TRANSPORT PAMANT IN EXCES, COMPACTARE, REFACERE TEREN ZONA AFECTATA LA STARE INTIALA, INCLUSIV BETONARI, PIETRUIT, ETC.-MATERIAL+MANOPERA)</i>			
10	MC	907.06	907.06
<i>NISIP -CONFORM CERINTE DISTRIBUTOR/LEGISLATIE IN VIGOARE PT. LUCRARI COND. GAZE NATURALE</i>			
11	BUC	180	180.00
<i>RASUFLATORI SPATIU VERDE/CAROSABIL</i>			
12	ML	70	70.00
<i>TUB PROTECTIE OL 168+IZOLATIE PE (CONFORM CERINTA DEIDISTRIBUTOR GAZ VEST)</i>			
13	BUC	1	1.00
<i>PIESE CUPLARE+MATERIALE MARUNTE</i>			
Cheltuieli directe din articole:			
Alte cheltuieli directe:			
COTA 2.25		2.25%	
Total cheltuieli directe:			
Cheltuieli indirecte		%	
Profit		%	
Total cheltuieli directe si indirecte:			

TOTAL MANOPERA+CHELTUIELI DIRECTE SI INDIRECTE+PROFIT
TOTAL MATERIAL
TVA 19%
TOTAL

